



# CITY AND COUNTY OF DENVER

Department of Public Works - Engineering Division

Wastewater Capital Projects Management

## STATEMENT OF QUANTITIES

**DENVER**  
THE MILE HIGH CITY

Project No. PC70809\_320

Contract No. CE90326

### 36th Avenue-High Street to Clayton Street Storm Sewer

Item #	Item Description	Additional Item Information	Est Qty	Units
2-1.2a	REMOVE 6" CONCRETE CURB AND/OR GUTTER		530	LF
2-1.4	REMOVE HANDICAP CONCRETE CURB RAMP		1,326	SF
2-2.1	REMOVE CONCRETE SIDEWALK		100	SF
2-3.4	REMOVE CONCRETE STREET INTERSECTION GUTTER (CROSSPAN) AND/OR VALLEY GUTTER		2,800	SF
2-11.2e	REMOVE EXISTING 18" STORM SEWER PIPE		360	LF
2-12.2	REMOVE EXISTING STORM MANHOLE		4	EA
2-13.1	REMOVE EXISTING STORM INLET		6	EA
5-2a	SUBGRADE MATERIAL (SELECT BACKFILL)		150	TON
8-1.1b	6" DIP AWWA C151, CLASS 50 WATER LINE		160	LF
8-1.1c	8" DIP AWWA C151, CLASS 50 WATER LINE		20	LF
8-1.1e	12" DIP AWWA C151, CLASS 50 WATER LINE		20	LF
8-1.2b	INSTALL 6" WATER VALVE		8	EA
8-1.2c	INSTALL 8" WATER VALVE		2	EA
8-1.2e	INSTALL 12" WATER VALVE		2	EA
12-1.1	VERTICAL 6" CONCRETE CURB AND GUTTER		122	LF
12-1.8	HANDICAP CONCRETE CURB RAMP		1,326	SF
12-2.1	CONCRETE SIDEWALK		100	SF
12-4.1	CONCRETE STREET INTERSECTION GUTTER (CROSSPAN)		448	SF
12-13	CONCRETE ENCASMENT AROUND PIPE		4	CY
20-1	ASPHALTIC TEMPORARY PATCHING		7,000	SY/IN
20-2be	ASPHALT OVERLAY, SX, RAP 20%, N=75, 64-22.		13,850	SY/IN
20-3be	ASPHALT TRENCH PAVING, S, RAP 20%, N=75, 64-22.		18,200	SY/IN
20-4	ASPHALT ROTOMILL		5,450	SY/IN
34-2.3d	15" DIAMETER C-76 RCP, CLASS III		117	LF
34-2.3e	18" DIAMETER C-76 RCP, CLASS III		680	LF
34-2.3f	21" DIAMETER C-76 RCP, CLASS III		88	LF

Contract No. CE90326  
36th & High

October 12, 2009



# CITY AND COUNTY OF DENVER

Department of Public Works - Engineering Division

Wastewater Capital Projects Management

## STATEMENT OF QUANTITIES

**DENVER**  
THE MILE HIGH CITY

34-2.3g	24" DIAMETER C-76 RCP, CLASS III		298	LF
34-2.3i	30" DIAMETER C-76 RCP, CLASS III		350	LF
34-2.3m	42" DIAMETER C-76 RCP, CLASS III		480	LF
34-5.4d	24" X 38" C-507 RCP, CLASS HE-III		334	LF
34-5.4h	34" X 53" C-507 RCP, CLASS HE-III		1,581	LF
34-12.1d	4' DIAMETER PRECAST MANHOLE WITH TYPE C BASE & FLAT TOP		13	EA
34-12.2d	5' DIAMETER PRECAST MANHOLE WITH TYPE C BASE & FLAT TOP		3	EA
34-12.4b	TYPE B MANHOLE WITH TYPE B TOP SLAB		14	EA
34-12.7	SPECIAL STRUCTURE	(MH-1, Special Design Type B)	1	EA
34-15.3	UTILITY EXPLORATORY INVESTIGATION		6	EA
34-16.1a	#14 STORM INLET (L=6')		2	EA
34-16.1c	#14 STORM INLET (L=12')		2	EA
34-16.2a	SINGLE #16 STORM INLET WITH OPEN THROAT		11	EA
34-16.3a	DOUBLE #16 STORM INLET WITH OPEN THROAT		8	EA
34-16.4a	TRIPLE #16 STORM INLET WITH OPEN THROAT		10	EA
40-3	SODDING		1,000	SF
41-1	TRAFFIC CONTROL		1	LS
43-1	STORM WATER MANAGEMENT PLANS (SWMPs)		1	LS
50-1	MOBILIZATION		1	LS