



6th Avenue Frontage Road Reconstruction

The 6th Avenue Frontage Road Reconstruction Project consists of rebuilding 1,200 feet of roadway. The project extends from 560 feet north of 6th Avenue and parallel to Sheridan south to 6th Avenue. The road then heads east 900 feet parallel to 6th Avenue and ends at approximately Xavier St. (if it were extended through the existing storage facility). The existing road is currently closed due to uneven settling of the pavement due to the road being built on an old landfill. The project will consist of rebuilding the road utilizing a green technology of recycling existing asphalt in place and mixing it with concrete for the new subgrade. New asphalt will then be placed on top. The road is being rebuilt to provide temporary access from the west during construction of the Wolff St. Bridge that is anticipated to start construction later this year. After the Wolff St. Bridge is built, the road will become a one-way street to the west.